Standby Generator with auto-transfer switch

Generator

Classic House, Thorndon

Standby Generator with auto-transfer switch

Accommodation			
Full Cabinets	42 Rack Units, 600 x 1000, vented doors front and rear	47 Rack Units, 600 x 1000, vented doors front and rear	
Housing options	Full, ½ racks	Full, ½, ¼ racks	
Floor	Vinyl covered concrete	te Vinyl covered concrete	
Ancillaries	Community keyboard and monitor provided	Community keyboard and monitor provided	
Power Supply			
Rack Supply	10amp at 240V/50Hz per cabinet (provided via a 10amp circuit breaker). Additional power available as per requirements.	10amp at 240V/50Hz per cabinet (provided via a 10amp circuit breaker). Additional power available as per requirements.	
UPS	Room UPS	Room UPS	

Environmental				
Air conditioning	n+1 redundancy, 22°C ±3° HVAC	n+1 redundancy, 22°C ±3° HVAC		
Fire Monitoring	Smoke Detectors	Smoke Detectors, Heat Detectors		

Cabling			
Cable Trays	Overhead racking	Overhead racking	
Access and Security			

Access and Security					
Access	24 / 7 card access system to building and facility	24 / 7 card access system to building and facility			
Rack Security	Customer lock	Customer lock (shared lock for community racks)			
Surveillance	Video Surveillance DVR	Video Surveillance DVR			